Nepal Engineering College

(Affliated to Pokhara University) Changunarayan, Bhaktapur

Summary of Quantities

S.N.	Description	Quantity	Unit
1	Earth work		
1.1	Earthwork(drain cut,slope cutting,structure cut) of ordinary soil	6,578.18	
	SubTotal	6,578.18	m³
1.3	Earthwork(ordinary fill/back fill) of ordinary soil	6,331.11	
	SubTotal	6,331.11	
1.4	Drain work(left/right)	3,203.98	
	SubTotal	3,203.98	m³
	Total	16,113.27	m ³
2	Masonary work		
2.1	Masonary Breast wall Volume(left)	377.90	
2.2	Masonary Breast wall Volume(right)	174.10	
	Total	552.00	m^3
3	Gabion retaining wall work(left\right)volume	1,181.40	
	Total	1,181.40	m ³
4	Dry Retaining wall work(left\right)	326.86	\mathbf{m}^3
	Total	326.86	\mathbf{m}^3
5	Plain and Reinforced Cement Concrete for Structures		
5.1	Supply and place concrete class M 10 (1:3:6)		
	Box culvert	4.00	
	Total	4.00	m ³
6	Sub-base, Base and Shoulders		
6.1	sub base material	3076.25	m³
6.2	Base course material	12305	m2